

Supplemental Table 1. Estimated labor costs employed in this study by task.

Activity	production per person day (p-d)	Source
Procurement of cobble fill	3.86 m ³ /p-d	Abrams 1994:44
Excavation of soil	2.6 m ³ /p-d	Abrams 1994:44
Earth transport 50 m	2.19 m ³ /p-d	Abrams 1994:48
Cobble transport 50 m	1.88 m ³ /p-d	Abrams 1994:48
Placement of fill	4.83 m ³ /p-d	Abrams 1994:44
Limestone masonry extraction and preparation	.028 m ³ /p-d	Woods and Titmus 1994:298-305 (person days adjusted to 5 hours)
Limestone transport	.278 m ³ /p-d	Weight per Woods and Titmus 1994:299
Block placement	3.2 m ² /p-d	Abrams 1994:51
Plaster preparation	.022 m ³ /p-d	Abrams 1994:49–51
Plaster transport	.31 m ³ /p-d	Abrams 1994:48
Plaster application	8 m ² /p-d	Abrams 1994:51